


EXCEPT AS OTHERWISE PROVIDED BY CONTRACT, THIS DRAWING AND SPECIFICATIONS SHALL NOT BE REPRODUCED, COPIED OR USED AS THE BASIS FOR MANUFACTURE OR SALE OF MATTER DEPICTED HEREIN WITHOUT THE EXPRESSED WRITTEN PERMISSION OF THE CLAUDE LAVAL CORPORATION, OR ITS ASSIGNEES.

NOTES:

1. OUTLET: 10" MALE NPT.
2. RATED FLOW: 1460-2040 gpm (323-463 m³/hr).
3. MINIMUM WELL I.D.: 15.25" (388 mm).
4. HEAD LOSS: 9-14 ft (2.7-4.3 m).
5. MINIMUM SUBMERGENCE: 60 ft (18.4 m).
6. APPROXIMATE DRY WEIGHT: 499 lbs (226 kg).
7. FINISH: POWDERCOAT LAKOS GREEN RAL-6018 (EXTERIOR ONLY).
8. IF UNIT IS NOT DIRECTLY CONNECTED TO PUMP INTAKE, SHROUD OR PACKERS ARE REQUIRED.



THIS DRAWING HAS BEEN GENERATED AND IS MAINTAINED BY A CAD SYSTEM. CHANGES SHALL ONLY BE INCORPORATED AS DIRECTED BY AN APPROVED ENGINEERING CHANGE ORDER (ECO). PAPER COPIES ARE UNCONTROLLED.

REVISIONS				
ZONE	REV.	DESCRIPTION	DATE	APPROVED



SUBMITTAL DRAWING

This drawing is submitted for spatial consideration only. Do not pre-plumb to these dimensions.

UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN: INCHES [mm] TOLERANCES ARE: FRACTIONS DECIMALS ANGLES ± 1/4" .XX ± .01 ± 1/4° .XXX ± .005 .XXXX ± .0005		ENGINEERED FOR: STANDARD		 CLAUDE LAVAL CORP. FRESNO, CALIFORNIA 93727 WWW.LAKOS.COM		 LAVAL UNDERGROUND SURVEYS	
DO NOT SCALE DRAWING		APPROVALS	DATE	TITLE			
MATERIAL CLASS P-1 MILD CARBON STEEL		DRAWN JBI	7/11/07	PPS-JSA, SEPARATOR JSA-PUMP PROTECTION, CARBON STEEL			
FINISH LAKOS GREEN		ENGR JBI	7/11/07	SIZE C	MODEL NO.	DWG NO.	REV.
		WORK ORDER	QTY.	SCALE 1:12	EST. WT. 499 lb	SHEET 1 OF 1	107648 01