

3

4

 \square

PAPER COPIES ARE UNCONTROLLED.

REVISIONS						
ZONE	REV.	DESCRIPTION DATE APPR				
-	F	CHG. MOTOR MOUNT & NEW STY STRAINER 7/13/2012 SUB				
-	G	CHANGE PUMP AND PUMP MOUNT	2/11/13	TRR		
	Н	REVISED CURRENT STD 4/15/2016		ADJ		
	J UPDATED BOLTS LENGTHS		6/7/2017	TRR		
K UPDATE SYSTEM AND CHNG PUMP AMP TO XYLEM 2/25/2020		TRR				

D

С


15424

<u>NOTES:</u>

- INLET IS 8" PIPE (125# ANSI FLANGED). 1.
- 2. OUTLET IS 6" PIPE (GROOVED).
- 3. PURGE OUTLET IS 1-1/2" PIPE.
- MAXIMUM PRESSURE: 150 psi (10.3 bar). 4.
- MAXIMUM TEMPERATURE: 100°F (37.8°C). 5.
- SPECIFIED FLOWRATE OF 1100 gpm (250 m³/hr). 6.
- FINISH: AS ASSEMBLED. 7.
- POWER REQUIREMENT: 460V, 3PH, 60Hz. 8.
- NEMA 4X MOTOR STARTER ENCLOSURE WITH 9. SAFETY DISCONNECT AND H.O.A. SWITCH.
- 10. APPROXIMATE DRY WEIGHT: 2163 lbs (981 kg).
- 11. INLET/OUTLET VALVE KIT, MODEL TCV-1100 RECOMMENDED.
- 12. MINIMUM PIPE FROM TOWER BASIN TO TC SYSTEM IS 10" PIPE.
- 13. FLOODED SUCTION REQUIRED.

COMPONENT LIST:

- (1) ELECTRICAL CONTROL BOX 460V 60Hz W/120V TRANSFORMER.
- $\overline{(2)}$ SEPARATOR: HTH-0500-TC.
- (3) PUMP: 40 HP CENTRIFUGAL, 1800 rpm, 460V, 60Hz.
- (4) INLET/OUTLET PRESSURE GAUGES: 0-160 psi, GLYCERIN-FILLED.
- (5) PURGE EQUIPMENT: SRV-816.
- (6) DIFFERENTIAL PRESSURE INDICATOR: (AVAILABLE WITH DRY DRY CONTACT-
- MODEL DHE-15-S. ORDER SEPARATELY).
- (7) BASKET STRAINER.



FRONT VIEW PUMP & STRAINER

ENGINEERED FOR: STANDARD		FRESNO, CALIFORNIA WWW.LAKOS.COM	
APPROVALS	DATE	FILTRATION SOLUTIONS	
DRAWN DLW	11/15/04		
ENGR DLW	8/29/07		
REVIEW _	-		
WORK ORDER	QTY.	C 115424 K SCALE 1:12 EST. WT. 2163 lb SHEET 1 OF 2	
	STANDARD APPROVALS DRAWN DLW ENGR DLW REVIEW -	STANDARD APPROVALS DATE DRAWN DLW 11/15/04 ENGR DLW 8/29/07 REVIEW - -	

2